QUOTATION

Quote No. **39312**

Baja Window Shading S. de R.L. de C.V.
Calle Camino Vecinal, # 5051
Col. Benito Juarez, C.P.22706
Playas de Rosarito, B.C., México.
Mex. Phone: +52 (664) 406-4229
USA Phone: 1 (619) 576-6826

Billing Information
Di Calabria Industries Inc.
9927 Via de la Amistad
San Diego, CA 92154
Contact: Yukiu Peralta
Phone: (619) 941-2700

US Receiving and Shipping Warehouse
Ruffo de Alba Forwarders, LP
9927 Via de la Amistad Business Park
San Diego, CA 92154
Contact: Pamela Vera
Phone: (619) 591-9391

TO: **HUNTER DOUGLAS HOSPITALITY**
Contact: **PATRICK AUSTIN**

Project Name: **H2S BREAKFAST SHADE**
Project Location:

Today's Date: 29-Jul-25
Quote Valid Until: 27-Sep-25

Item	Qty	UOM	Description	Room / Area	Finished Width	Finished Length	TOTAL EA.	TOTAL ALL
1	1	EA.	**MOTORIZED BLACKOUT ZIPPER SYSTEM ROLLER SHADE**	BREAKFAST SHADE	337.000	66.000	$ 4,480.00	**$ 4,480.00**
	1	EA.	**STYLE:** MOTORIZED ZIPPER ROLLER SHADE WHITE BOX FASCIA AND CHANNELS,			**SPECIAL CRATING**	$ 350.00	**$ 350.00**
			WEIGHT TYPE: EXTERNAL WEIGHT BAR					
			MOUNT: INSIDE MOUNT					
			HARDWARE: ASSEMBLED **SPLITTED** TUBE WITH **HARDWIRED** SOMFY MOTOR, WITH PROPER BRACKETS.					
			CONTROL TYPE: **C.O.M.** / ROCKET SWITCH.					
			FABRIC: **COM / PRINTED BLACKOUT 118"W (RAILROADED)** **TOTAL COM YDGE REQ. = 11YDS**					
							Total Item 1=	**$ 4,830.00**

GRAND TOTAL= $ 4,830.00

PRICES ARE FOB SAN DIEGO CA., FREIGHT NOT INCLUED. PACKAGING INCLUDED. DUTIES FOR EXPORTATION OF FINISHED GOODS ARE INCLUDED **(ADDITIONAL DUTY CAN BE ADDED IF PRESIDENT TRUMP ANNOUNCES AS A DECRET, TARIFF NOT INCLUDED, TO BE PAID SEPARATELY).**

LEAD TIME 10-12 WEEKS AFTER RECEIVING P.O., PREPAYMENT, C.O.M. FABRICS AND RECAP APPROVAL

PAYMENTS TERMS: 50% PREPAYMENT + 50% BALANCE NET 15 DAYS.

LATE FEES: 5% MONTHLY INTEREST FOR 30-60 DAYS, 8% MONTHLY INTEREST FOR 60-90 DAYS AND 12% MONTHLY INTEREST FOR 90-120 DAYS

ZIPPER SYSTEM DISCLAIMERS AND BUILDING TOLERANCES:

To ensure light blockage and prevent fabric wrinkling, the window sill must be level and the zipper system must hang straight. The roller blind must travel freely downward.
It is important that the inner zip profile is always mounted vertically and perpendicular to the blind tube so that the fabric can roll down freely through the zipper
The angle between the window sill and the side guide must be ≤ 90°
The inner zip guide can handle a tolerance of 10mm (2/5") per side guide
*If installation tolerances cannot be met, an L-profile in a matching color can be ordered from BWS to cover the gap between the side channel and the wall.
*Installation of the zipper system requires a professional trained installer.

Quoted by: **Abel Salazar**