



# QUOTATION

Quote No. **39682**

**Baja Window Shading S. de R.L. de C.V.**

Calle Camino Vecinal, # 5051  
Col. Benito Juarez, C.P.22706  
Playas de Rosarito, B.C., México.  
Mex. Phone: +52 (664) 406-4229  
USA Phone: 1 (619) 576-6826

**Billing Information**

Di Calabria Industries Inc.  
9927 Via de la Amistad  
San Diego, CA 92154  
Contact: Yuki Peralta  
Phone: (619) 941-2700

**US Receiving and Shipping Warehouse**

Ruffo de Alba Forwarders, LP  
9927 Via de la Amistad Business Park  
San Diego, CA 92154  
Contact: Pamela Vera  
Phone: (619) 591-9391

TO: HUNTER DOUGLAS HOSPITALITY  
Contact: PATRICK AUSTIN

Project Name: H2S BREAKFAST - GOODYEAR, AZ  
Project Location: GOODYEAR, AZ

Today's Date: 11-Nov-25  
Quote Valid Until: 10-Jan-26

Item	Qty	UOM	Description	Room / Area	Finished Width	Finished Length	TOTAL EA.	TOTAL ALL
1	1	EA.	<b>MOTORIZED BLACKOUT ZIPPER SYSTEM ROLLER SHADE</b>	BREAKFAST SHADE	253.000	64.125	\$ 3,270.00	\$ <b>3,270.00</b>
	1	EA.	STYLE: MOTORIZED ZIPPER ROLLER SHADE WHITE BOX FASCIA AND CHANNELS,		SPECIAL CRATING		\$ 350.00	\$ <b>350.00</b>
			WEIGHT TYPE: EXTERNAL WEIGHT BAR					
			MOUNT: INSIDE MOUNT					
			HARDWARE: ASSEMBLED <b>SPLITTED</b> TUBE WITH <b>HARDWIRED</b> SOMFY MOTOR, WITH PROPER BRACKETS.					
			CONTROL TYPE: <b>C.O.M.</b> / ROCKET SWITCH.					
			FABRIC: <b>COM / PRINTED BLACKOUT 118"W (RAILROADED)</b> TOTAL COM YDGE REQ. = 8YDS					
							<b>Total Item 1=</b>	<b>\$ 3,620.00</b>

PRICES ARE FOB SAN DIEGO CA., FREIGHT NOT INCLUDED. PACKAGING INCLUDED. DUTIES FOR EXPORTATION OF FINISHED GOODS ARE INCLUDED (ADDITIONAL DUTY CAN BE ADDED IF PRESIDENT TRUMP ANNOUNCES AS A DECRET, TARIFF NOT INCLUDED, TO BE PAID SEPARATELY).

**GRAND TOTAL= \$ 3,620.00**

LEAD TIME 10-12 WEEKS AFTER RECEIVING P.O., PREPAYMENT, C.O.M. FABRICS AND RECAP APPROVAL

**PAYMENTS TERMS:** 50% PREPAYMENT + 50% BALANCE NET 15 DAYS.

**LATE FEES:** 5% MONTHLY INTEREST FOR 30-60 DAYS, 8% MONTHLY INTEREST FOR 60-90 DAYS AND 12% MONTHLY INTEREST FOR 90-120 DAYS

**ZIPPER SYSTEM DISCLAIMERS AND BUILDING TOLERANCES:**

To ensure light blockage and prevent fabric wrinkling, the window sill must be level and the zipper system must hang straight. The roller blind must travel freely downward.

It is important that the inner zip profile is always mounted vertically and perpendicular to the blind tube so that the fabric can roll down freely through the zipper

The angle between the window sill and the side guide must be  $\leq 90^\circ$

The inner zip guide can handle a tolerance of 10mm (2/5") per side guide

\*If installation tolerances cannot be met, an L-profile in a matching color can be ordered from BWS to cover the gap between the side channel and the wall.

\*Installation of the zipper system requires a professional trained installer.

Quoted by: Abel Salazar